

# TRUCKEE RIVER WATERSHED COUNCIL

---

PO Box 8568  
Truckee, CA 96162  
530-550-8760  
[www.truckeeriverwc.org](http://www.truckeeriverwc.org)

January 9, 2019

## Martis Wildlife Area Restoration Project Request for Bids: Construction

### Addendum 1

The Work included in this Request for Bids is amended to include the following:

#### Work

Deliver and install up to 25,000 square feet of propagated revegetation mats. Propagated mats are coir (coconut fiber) mats that have been hydroponically grown with rhizomatous wetland plant species.

The Contractor will install the propagated revegetation mats along the wet edges and secondary channels of Martis Creek (Site 1) at the direction of the Engineer and CPESC.

Planting locations will be as directed by the Engineer and CPESC. TRWC will not provide drawings or any spatial representation of planting locations. Locations will be staked in the field by the Engineer and CPESC. The Contractor shall notify the Engineer two working days in advance of any installation to provide time for layout and staking.

Installation will be as directed by the Engineer and CPSEC. In general, installation will follow the details and specifications for coir mat installation respectively on Sheet 5.0 and 5.2 of Attachment 1 to the RFB. Installation and transport within planting areas shall be completed by hand to minimize damage to the propagated revegetation mats.

#### Materials

Contractor will furnish labor, materials, equipment, tools, and incidentals as necessary to complete this work and comply with permits including delivery of up to 25,000 square feet of propagated mats from the Nevada Division of Forestry's Washoe State Tree Nursery.

TRWC will provide:

- Propagated revegetation mats, up to 25,000 square feet

#### Cost

Provide cost on a lump sum basis.