

TRUCKEE RIVER WATERSHED COUNCIL

PO Box 8568
Truckee, CA 96162
530-550-8760
www.truckeeriverwc.org

Lower Lacey Meadow Construction RFB Addendum 1 – Response to Questions November 22, 2023

1. Is a construction entrance needed?

No, a construction entrance will not be required as access from the staging area to the work area is via dirt roads. The Bid Sheet has been revised to remove that item.

2. Is construction fencing needed?

The limits of the staging area(s) need to be marked in some fashion. An alternative to orange construction fencing is acceptable – for example T-posts and rope. No other work areas need to be fenced. The “construction limit fencing” line item remains on the revised Bid Sheet.

3. Will a revised bid sheet with quantities be provided?

The Bid Sheet has been revised and is attached to this addendum. We have included an estimate for the amount of aggregate import required for surfacing the filled sections of Webber Lake Road (200 cubic yards).

Bid Sheet - Revised Nov. 22, 2023
Lower Lacey Meadow Restoration

Design Team: Balance Hydrologics (civil engineer/geomorphologist)
HT Harvey (revegetation specialist)

Quantities By: _____ **Date:** _____

Bid Item #	CONTRACT ITEMS	UNIT	QTY	UNIT COST	TOTAL COST
1	Environmental Requirements				
1a	Construction Limit Fencing	LF			
1b	Temporary Wattles	LF			
1c	Meadow Protection Mats, 14' wide	LF			
1d	Temporary Stream Crossing	EA			
1e	Fish Rescue and Relocation	LS			
2	Mobilization and Demobilization	LS			
3	Temporary Diversion and Dewatering	LS			
4	Pilot Channel Excavation	CY			
5	Webber Lake Road Fill	CY			
6	Fine Grading	SF			
7	Sod Harvest and Placement	SF			
8	Debris Jam Type 1 - Bundle	EA			
9	Debris Jam Type 2 - Small Log Jam	EA			
10	Debris Jam Type 3 - Standard Large Log Jam	EA			
10a	Debris Jam Type 3 at Pilot Channel 1 (inc. log posts)	EA			
10b	Debris Jam Type 3 at Pilot Channel 2 (inc. log posts)	EA			
11	Debris Jam Type 4	EA			
12	Debris Jam Type 5	EA			
13	Rolling Dips	EA			
14	Willow Salvage and Planting (clumps and stakes)	LS			
15	Seeding	SF			
16	Erosion Control Blanket	SF			
17	Aggregate Import, Webber Lake Road - est. 200 cy	CY			
18	Revegetation Maintenance (2 year maintenance period)	YR			
	TOTAL				

Fuel Cost Used in Bid: